Capsule Summary SM-584 Hayden Garage Laurel Grove Private

c. late-1930's

In 1935, Joseph L. and Mary V. Hayden purchased a 1 1/2 acre tract on the southwest side of Route 235 (Old Three Notch Road) in Laurel Grove, Maryland and soon after constructed a one story, rusticated concrete block garage with a gambrel roof. Since it was initially constructed, the garage has served many purposes. At different times it was used as an automobile showroom, automobile repair painting facility, as well as a blacksmith shop. While enlarged in 1946-1947, the building's alterations have been sympathetic to its original appearance. A rear addition, for instance, was constructed using the identical type of concrete block. Its architectural integrity as well as its association with the emergence of automobile travel, repairs, and sales, makes the garage a significant example of 1930's roadside architecture.

Joseph L. Hayden, Sr., a local blacksmith, originally constructed the building in the late-1930's. Hayden used the garage to shoe horses and make other metal parts and repairs to farm implements. Hayden also used the garage as an automobile repair and paint shop. According to Joseph and Mary Hayden's daughter-in-law, Nellie Hayden, the garage was enlarged just after the end of World War II when Nellie's husband Joseph L. Hayden, Jr. returned from the service with the Navy in Europe, having taken part in the invasion on Normandy. The property remained in the Hayden family until 1989.

Maryland Historical Trust HISTORIC PROPERTIES State Historic Sites Inventory Form

MARYLAND INVENTORY OF

Survey No. SM-584

Magi No.

DOE __yes __no

<u>1. Nam</u>	e (indicate pr	eferred name)		
nistoric				
and/or common	Hayden Garage (pre	ef.) Laurel Grove Us	ed Auto Cars Garage	
2. Loca	ation			
0.1 mile S street & number	of the int. of Rout	ce 235 & Morganza-La	urel Grove Road, or	the W side of Rt 2
city, town Lau	arel Grove	vicinity of	congressional district	6
state Maryla	and	county	St. Mary's	TM-14, P-64
3. Clas	sification			
Category district building(s) structure site object	Ownership public private both Public Acquisition in process being considered not applicable	Status occupied unoccupied work in progress AccessibleX yes: restricted yes: unrestricted no	Present Use agriculture commercial educational entertainment government industrial military	museum park private residence religious scientific transportation X other: storage
	er of Prope	rty (give names a	nd mailing addresse	s of <u>all</u> owners)
-,	y R. Alvey 26985 Three Notch	Pond	tolophono n	•••• 301–475–4662
city, town Mec			and zip code Maryl	and 20659
5. LUC	ation of Leg	al Description)(1	
courthouse, regi	stry of deeds, etc. St.	Mary's County Court	house	liber EWA 1134
street & number				folio 441
city, town	Leonardtown		state	Maryland
6. Rep	resentation	in Existing	Historical Surv	eys
title				
date			federal stat	te county local
depository for su	urvev records			
	a. vay rooorda			
city, town			state	

7. Description

Survey No. SM-584

Condition excellent deteriorated _X good ruins fair unexposed	Check one unaltered _X_ altered	Check oneX original site moved date of move	
---	---------------------------------	---	--

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Contributing Resource Count: 1

The Hayden Garage is located on the south side of Route 235 approximately 1.0 mile north of the intersection of Route 235 and Loveville Road (Route 247). The garage is oriented on a southwest/northeast axis and is situated only fifteen feet from the road. It is bounded on the northeast and southwest by single family residences and a field to the northwest.

The Hayden Garage is a one-story, rusticated concrete block building with a gambrel, raised-seam metal roof that is pierced by three interior brick chimney flues. Initially constructed in 1939, the rear section of the garage was erected using similar concrete block in 1946.

The northeast or primary elevation is pierced by a twelve light window and a three panel, four light door. At the southern corner of the elevation several metal sheets cover a section of the front that was damaged when a car crashed into it. This section featured a garage door. Four boarded over window panes mark the location of the door.

The northwest elevation is pierced by three, six-over-six, double-hung sash windows, three window openings that have been boarded-up, and a door. A pair of seams mark the location of a garage opening that was closed up probably during the 1946 addition. Another seam in the enclosed cornice and wall marks the transition between the original front section and rear addition.

The southwest elevation is pierced by a six-over-six window, a boarded up window, and a northwestly sliding, wood garage door.

The southeast elevation is pierced by four boarded-up windows, a wood door, and a pair of swinging garage doors with a one light transom above. This elevation also features a seam in the enclosed comice and wall that marks the transition between the original building and the addition. Near the southwestern corner of the building are a series of six concrete columns of descending height that extend from the ground to about three feet high. Used as a car ramp and support, the columns no longer feature top supports for the car and are free standing fromt the building.

The interior is divided into two spaces--a large workroom and an office. The office was not accessible at the time of the visit. The workroom, however, is distinguished by a poured concrete floor, walls of the same rusticated concrete block, and an exposed structural system for the roof. A section of the original rear wall survives roughly at the middle of the building. This wall serves as the support for a steel I-beam that carries the weight of the roof. The I-beam supports a series of trusses composed of three struts that extend from the I-beam to the roof rafters. While the building features a gambrel roof, the framing does not feature any purlins as the rafter sets are merely lapped against each other to create the change in roof pitch. An interior brick chimney stack covered with cement contains the numerals "1901." According to Nellie Hayden, however, the garage was built by her husband's father Joseph L. Hayden. The building is currently used for storage and a restoration is planned.

8. Significance					_	Survey No. SM-584			
Period pret 1500 1500 1500 1500 1500 1500 1500 150	nistoric ar 0-1499 ar 0-1599 ag 0-1699 ar 0-1799 ar 0-1899 co	of Significance— cheology-prehistoric cheology-historic griculture chitecture t ommerce ommunications	c co co ec en ex ind	mmunity inservation conomics lucation igineering ploration	planning on		law litera milita musi philo	ary ic	re religion science sculpture social/ humanitarian theater transportation other (specify
Specific	: dates		Builde	r/Archit	ect				
check:	and/or	Criteria: \underline{x} . Exception:	AB A B		D D	E	F	G	

Cianificance

Prepare both a summary paragraph of significance and a general statement of history and support.

Level of Significance: national state X local

In 1935, Joseph L. and Mary V. Hayden purchased a 1 1/2 acre tract on the southwest side of Route 235 (Old Three Notch Road) in Laurel Grove, Maryland and soon after constructed a one story, rusticated concrete block garage with a gambrel roof. Since it was initially constructed, the garage has served many purposes. At different times it was used as an automobile showroom, automobile repair painting facility, as well as a blacksmith shop. While enlarged in 1946-1947, the building's alterations have been sympathetic to its original appearance. A rear addition, for instance, was constructed using the identical type of concrete block. Its architectural integrity as well as its association with the emergence of automobile travel, repairs, and sales, makes the garage a significant example of 1930s roadside architecture.

Joseph L. Hayden, Sr., a local blacksmith, originally constructed the building in the mid-1930s. Hayden used the garage to shoe horses and make other metal parts and repairs to farm implements. Hayden also used the garage as an automobile repair and paint shop. According to Joseph and Mary Hayden's daughter-in-law Nellie Hayden, the garage was enlarged just after the end of World War II when Nellie's husband Joseph L. Hayden, Jr. returned from the service with the Navy in Europe, having taken part in the invasion on Normandy. The property remained in the Hayden family until 1989.

Interview. Harry R. Alvey, April, 1997.

10. Geographi	cal Data					
Acreage of nominated property _ Quadrangle name Mechanicsvi UTM References do NOT com				Quadrangl	le scale 1:24 000	
40 1101 6011	plete UTM refe					
Zone Easting No	rthing	B Zon	e Eas	sting	Northing	
		ם 🔟			1.1.1.1.1	
E L		F	ĪŪ			
G L L		н 🗔				
Same as per deed description. List all states and counties for state	or properties over	iapping state o	r count	y boundaries	code	
state	code	county			code	
11. Form Prep	ared By					
name/title Kirk E. Ranzetta, Hi	storic Sites Surve	yor				
organization St. Mary's County	Dept. of Planning	and Zoning	date	5-19-97		
street & number 22740 Washing	ton Street		teleph	one 301-475-4	662	
city or town Leonardtown			state	Maryland		

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust

Shaw House
21 State Circle

Annapolis, Maryland 21401

(301) 269-2438

DHCP/DHCD 100 COMMUNITY FLACE OWNSVILLE, MD 21032-2023 -514-7100

SM-584, Hayden Garage

St. Mary's County 8.1 Significance

Chain-of-Title

(All deeds are located at the Land Records Office, St. Mary's County Courthouse, Leonardtown, Maryland unless otherwise noted.)

Reference: Liber EWA 1134, Folio 441

Grantee: Harry R. Alvey

Grantor: William Roger and Stacy Lynn Alvey

Date: February 28, 1997

Notes: The property consists of .7983 acres. It was surveyed by Robert E. Trautman on February

3, 1997.

Reference: Liber MRB 512, Folio 487

Grantee: William Roger and Stacy Lynn Alvey

Grantor: Joseph L. Hayden III and Sherry A. Hayden

Date: December 28, 1989

Reference: Liber MRB 409, Folio 83

Grantee: Joseph L. Hayden III and Sherry A. Hayden

Grantor: Mary V. Hayden Date: April 28, 1988

Notes: On March 2, 1965, Joseph L. Hayden, Sr. died leaving the 1 1/2 acre property to his

widow Mary.

Reference: Liber JMM 9, Folio 287 Grantee: Joseph L. and Mary V. Hayden

Grantor: Annie E. McGinley Date: August 30, 1935

Reference: Liber JFF 10, Folio 89 Grantee: Annie E. McGinley

Grantor: John N. Graves--administrator of Susan Bond's estate

Date: April 9, 1887

Notes: As a result of an equity case #622 NE between John Graves and John W. Bond, the land called Lot #1 containing 11 1/4 acres, is sold to Annie McGinley. No previous deed is listed.

SM-584, Hayden Garage St. Mary's County Maryland Comprehensive State Historic Preservation Data

Historic Context Geographic Organization:

Western Shore

Chronological/Developmental Period:

Break with the Past, 1930-present

Historic Period Theme:

Architecture Commercial

Resource Type Category:

Building

Historic Environment:


Rural

Historic Function and Use:

Automobile Repair and Blacksmith Shop

Known Design Source:

None





SM-684 Hogd manis County Bick Rangella 150 2 11 PG N+ N element



la oden sais e Marile Couries Ma = 1497 MA = HPO